# BRUHATH BENGALURU MAHANAGARA PALIKE

Yelahanka Division, Yelahanka Zone

Executive Engineer
Yelahanka Division
B.B.M.P. Bengaluru - 64
No EE/YNK.D/E-PMT/06/2013-14 date: 5-11-2013.

## (MODIFIED ) APPROVED TENDER SCHEDULE –'B'

Item No: 67

Name of Work:-Providing of BS slab drain at Anubha bhavani temple road from Sambram college to Subbash Chandra Bose road in Attur, ward no:03

| Sl | Description | Unit | Approved Qty | Rate Quoted By the Contractor Approved Rates Sri K CHANNAKESHAVAMURTHY | |
|---|---|---|---|---|---|
| | | | | Approved | Rates in words |
| 1 | KSRB 2-2.2:Earthwork excavation for foundtion of buildings, water supply, sanitary lines and electrical conduits either in pits or in trenches 1.5m and above in width, in ordinary soil not exceeding 1.5m in depth including dressing the bottom and sides of pits and trenches, stacking the excavated soil clear from edges of excavation with lead upto 50m, after breaking of clods complete as per specifications Specification | Cum | 396.66 | 200.00 | Rupees two hundred and paise zero only |
| 2 | Providing 7.5 cm thick granite slabs of selected quality roughly dressed and fixed in cement mortar (1:6) including fixing curing etc., complete | Sqm | 1002.00 | 315.00 | Rupees Three hundred fifteen and paise zero only |
| 3 | KSRB 4-1.3:Providing and layingin position plain cement concrete of mix M7.5 with OPC cement @ 180 kgs, with 40mm and down size graded granite metal coarse aggregates @ 0.85 cum and fine aggregates @ 0.57 cum machine mixed, concrete laid in layers not exceeding 15 cms, thick well compacted, in foundation and plinth including cost of all materials, labour, HOM of machienry, curing complete as per specifications Specification | Cum | 15.22 | 4000.00 | Rupees Four thousand and paise zero only |
| 4 | KSRB 5.2-3:Providing and constructing granite / trap / basalt size stone masonry in foundation cement mortar 1:6 stone hammered dressed in courses not less than 20 cms high, bond stones at two m. apart in each course including cost of materials, labour, curing complete as per specifications. | Cum | 38.45 | 3300.00 | Rupees three thousand three hundred and paise zero only |
| 5 | Providing ruled pointing of coursed stone masonry with Cement mortar 1:3 20mm deep, after raking joints to depth of 20mm necely lining, including cost of materials, abour, HOm of machineries curing etc., complete as per specification and directions of the Engineer-in-charge | Sqm | 64.08 | 25.00 | Rupees twenty five and paise zero only |

Executive Engineer,

| Sl | Description | Unit | Approved Qty | Rate Quoted By the Contractor Approved Rates Sri K CHANNAKESHAVAMURTHY | |
|---|---|---|---|---|---|
| 6 | KSRB 4-1.6 Providing and laying in position plain cement concrete of mix M15 with cement @240kgs with 20mm and down size graded granite metal, coarse aggregate @0.878cum and fine aggregate @0..459 cummachine mixed, concrete laid in layers not exceeding 15 cms, thick well compacted, in foundation, plinth and cills, including cost of all materials, labour, HOM of machinery, curing complete as per specifications. | Cum | 9.61 | 4700.00 | Rupees four thousand seven and paise zero only |
| 7 | KSRB 4.2.2 Providing and laying in position reinforced cement concrete of design mix M20 with OPC cement @ 320 Kgs, with 20mm and down size graded granile metal coarse aggregates @0.878 cum and fine aggregates @ 0.459 cum, with superplastisiser @ 3lts confirming to IS 9103-1999 Reaffirmed -2008, machine mixed, concrete laid in fayres not exceeding 15 cms, thick vibrated for all works in foundaton plinth and ground floor level for roof slabs, staircase,lintles, retaining walls, return walls. walls (any thickness) including attached plasters, columns, piers, abutments, pillars, posts, struts, buttresses, string or lacing courses, parapels, coping, bed blocks, anchor blocks, plain window cills fillets etc, including cost of all materials, labour, HOM of machinery, curing complete as per specifications. | Cum | 22.11 | 5300.00 | Rupees five thousand three hundred and paise zero only |
| 8 | KSRB 4.9-1:Providing T.M.T Steel reinforcement for RCC Work including straightening, cutting, bending hooking, placing in position, lapping and/or welding wherever required, tying with binding wire and anchoring to the adjoining members wherever necessary complete as per design (laps, hooks and wastge shall not be measured and paid) cost of materials, labour, HOM of machinery complete as per specifications. Specification No.KBS 4.6.3 | Qntl. | 21.38 | 7200.00 | Rupees seven thousand two hundred and paise zero only |
| 9 | KSRB 4-6.4 Providing and removing centering, shuttering, strutting proppoing etc, and removal of formwork for Vertical surface such as walls at any thickness including attached pilasters buttresses, plinth and string courses cost of all materials, labour complete as per specifications. Specification | Sqm | 63.23 | 200.00 | Rupees two hundred and paise zero only |
| 10 | KSRRB M100-1 Loading and unloading of stone boulder/stone aggregates/sand/ kanker/moorum. KSRRB M100-1:Placing tipper at loading point, loading with front end loader, dumping, turning for return trip, excluding time for haulage and return trip complete as per specifications. MORTH Chapter | Cum | 396.66 | 85.00 | Rupees eighty five and paise zero only |

Signature of the Contractor

Executive Engineer,
Yelahanka Division,
BBMP, Bangalore.